

February 16, 2024

**Jared M. Charland**

Project & Facilities Manager | City of Dubuque  
2200 Bunker Hill Road  
Dubuque, Iowa 52001  
563-690-6135  
[www.cityofdubuque.org/leisureservices](http://www.cityofdubuque.org/leisureservices)

RE: Grand River Center Parking Garage Lighting Replacement - #3346000004 **ADDENDUM #1**  
RDG: 3005.984.00

The following information is provided for incorporation or modification to the original documentation as included in the RFB distributed for bid on February 7, 2024. Bidder shall include a signed copy of this form in their bid as assurance that they have received it, understood it and incorporated any/ all changes into their respective bids.

**ADDENDUM #1**

Changes to the drawings (SHEET EL1.10) – Included in the original RFB as Attachment G:

- **ADD** designation “-E” to fixtures as shown on the drawing and noted on the sheet. These fixtures are the same product as standard TYPE PA and PB fixtures. However, they should be circuited to a “normally on” circuit with an additional UL924 GTD installed in-line to switch power over from the normally on circuit to the emergency circuit within the existing fixtures currently fed out of panel ELS in Room 105. Provide Bodine GTD20A or equivalent product.
- **ADD** three (3) Type PA-E to the project in locations as shown on the drawings.
- **REVISE** one (1) Type ER to Type PA-E at the entrance to the building as shown on the drawings
- **REVISE** quantities of fixture types in the table as shown on the drawings.
- **UPDATED** Sheet EL1.10 (Attachment G) is distributed with this addendum.

Other clarifications and information provided at the pre-bid walk-thru.

- Contractor will be responsible for the additional scope of removing and abandoning the 5-button control station located in Janitor 120. Verify that no additional control devices are relying on this control device for network signal or low-voltage power prior to removal. Provide jumpers within the existing box if required.
- All lighting in the garage is currently fed from Breakers #1 and #3 in Panel LS located in Electrical Room 105.
- No additional work on exit signs or any other lighting, electrical or building systems within the garage is to be included in the contractor's base bid. The owner reserves the right to request a change-order from the contractor should additional scope be added to this project.

**Attachments and enclosures**

- As-Built electrical lighting drawing sheets (dated 07-15-2002)
  - EL2-1B First Floor Plan – Area “B” - LIGHTING
  - EL2-1C First Floor Plan – Area “C” – LIGHTING
- Sheet EL1.10 (Attachment G)

Received and understood:

Signed \_\_\_\_\_

Dated \_\_\_\_\_

